



Regione Autonoma della Sardegna  
Assessorato dell'Industria  
Direzione Generale  
Viale Ferraro, n. 199 - 09121 Cagliari

ALL. 1

RECEIVED  
ME. 12.11.03  
501

Elab. 3-3  
Fm. N. 17443  
Ripresenta al foglio

nuovo

Espl. n. 4 27 NOV. 2003

del

• **Oggetto:** STUDIO DI FATTIBILITÀ PROGETTO INTEGRATO MINIERA CARBONIFERA-CENTRALE.

Alla SOTACARBO S.p.A.  
Località Portovesme  
09010 PORTOSCUSO

• Si fa riferimento alla nota n°463/03 in data 12 c.m. di codesta Società relativa all'argomento in oggetto per confermare, come già anticipato dal rappresentante della R.A.S. nel Comitato Tecnico Dott. Luigi Fadda, l'autorizzazione all'utilizzo dei dati progettuali elaborati da ATI Sulcis nell'ambito del progetto miniera - impianto di gassificazione, già in possesso di codesta Sotacarbo.

• *Il Direttore Generale*  
• Dott. Marco Murgia •



**TABLE OF CONTENTS**

1	EXECUTIVE SUMMARY .....	1
1.1	General .....	1
1.2	Geology .....	2
1.3	Resource and Reserve Estimates .....	2
1.4	Hydrogeology and Water .....	3
1.5	Environment .....	3
1.6	Mine Infrastructure .....	3
1.7	Geotechnical Design .....	3
1.8	Mechanical and Electrical Review .....	4
1.9	Coal Preparation Plant Review .....	4
1.10	SRK Mine Design .....	4
2	INTRODUCTION .....	7
3	TERMS OF REFERENCE .....	8
4	DESCRIPTION OF CURRENT MINE .....	8
5	GEOLOGY .....	15
5.1	GEOLOGICAL REVIEW .....	15
5.2	GENERAL GEOLOGY .....	15
5.2.1	Geological Setting .....	15
5.2.2	Productive Formation .....	16
5.2.3	Seam Correlation and Nomenclature .....	18
5.2.4	Structures .....	23
5.3	MINING HISTORY .....	26
5.4	PERMITTING .....	26
5.5	DRILLING AND EXPLORATION DATA .....	27
5.5.1	Surface Drilling .....	27
5.5.2	Geophysical Logging .....	28
5.5.3	Underground Drilling .....	28
5.5.4	Other Exploration Data .....	29
5.6	DATA RECORDING .....	29
5.7	COAL QUALITY .....	30
5.7.1	Product Requirements .....	30
5.7.2	Analysis of ANC .....	31
5.7.3	Coal Analysis (Chemical) .....	31
5.7.4	Petrographic Analysis .....	32

	5.7.5	Chemical Analysis Results.....	32
	5.7.6	Washing Tests.....	33
5.8		FUTURE EXPLORATION .....	34
5.9		GEOLOGICAL STAFFING.....	35
5.10		GEOLOGY CONCLUSIONS AND RECOMMENDATIONS .....	35
6		RESOURCE AND RESERVE ESTIMATES.....	38
6.1		PREVIOUS RESERVE STATEMENTS.....	38
6.2		INTERNATIONAL STANDARDS .....	38
6.3		SRK RESERVE ESTIMATE (1999).....	43
7		INFRASTRUCTURE.....	54
7.1		Surface Installations .....	54
7.2		Underground Structure and Installations .....	57
8		HYDROGEOLOGICAL AND WATER ASPECTS OF SULCIS MINE.....	60
8.1		Introduction.....	60
	8.1.1	Scope of Work.....	60
	8.1.2	Approach.....	60
	8.1.3	Data Sources .....	61
8.2		Site Details.....	61
	8.2.1	Topography.....	61
	8.2.2	Hydrology.....	61
	8.2.3	Climate .....	62
	8.2.4	Geology .....	62
8.3		Hydrogeology.....	63
	8.3.1	Conceptual Hydrogeological Model .....	63
	8.3.2	Water chemistry .....	66
	8.3.3	Other Hydrogeological Issues .....	66
8.4		Mine Inflows .....	67
	8.4.1	Inflows to the lower levels.....	67
	8.4.2	Inflow to the drift .....	68
	8.4.3	Future inflows.....	68
8.5		MINE SITE WATER MANAGEMENT .....	69
	8.5.1	Water supply.....	69
	8.5.2	Predicted future site water requirements .....	69
	8.5.3	Future supply versus demand summary .....	71
	8.5.4	Outputs from the site .....	71
8.6		Summary and Conclusions.....	72
8.7		Recommendations .....	73

9	ENVIRONMENT .....	74
9.1	Environmental Audit Procedures .....	74
9.2	Relevant Legislation .....	74
9.2.1	Italian/Sardinian .....	74
9.2.2	European Union .....	75
9.3	Current Environmental Conditions .....	77
9.3.1	Seruci mining area .....	77
9.3.2	Nuraxi Figus mining area .....	78
9.3.3	Key environmental issues .....	78
9.4	Baseline Geochemistry .....	79
9.5	Waste Disposal Issues .....	80
9.5.1	Coal tailings disposal.....	80
9.5.2	Coarse rejects disposal.....	82
9.5.3	Power plant waste disposal.....	82
9.6	Closure and Rehabilitation Cost Estimates .....	82
9.6.1	Summary of rehabilitation costs .....	83
9.6.2	Closure and rehabilitation activity cost estimates.....	85
9.6.3	Estimated costings .....	86
9.7	Other Issues Identified.....	89
9.8	Environmental Conclusions .....	91
10	GEOTECHNICAL DESIGN .....	93
10.1	GEOLOGICAL SETTING .....	93
10.2	DESCRIPTION OF THE SITE .....	94
10.2.1	WO10's Panel .....	94
10.2.2	WO12's maingate .....	95
10.2.3	S2's Gallerie di Testa .....	95
10.2.4	Main Return Gallery .....	95
10.2.5	Main Intake Gallery .....	95
10.3	OTHER GEOTECHNICAL ASPECTS .....	95
10.3.1	WO10's Face Stop Line .....	95
10.3.2	Inter Panel Pillars.....	96
10.3.3	Salvage of WO10's Face Line.....	98
10.4	COMMENTS ON THE CURRENT SUPPORT SYSTEM .....	98
10.5	ROCKBOLTING - GENERAL PRINCIPLES.....	98
10.5.1	Types of Rockbolts .....	104
10.5.2	Types of Bolt Considered for Sulcis .....	104
10.5.3	Design Methods .....	105
10.5.4	Type of Design Method Considered for Sulcis .....	105
10.6	SUITABILITY FOR ROOFBOLTING .....	106

	10.6.1	Initial Design.....	107
	10.7	TRAINING COURSES AND SUPERVISION .....	109
	10.8	IMPLEMENTATION PROGRAMME.....	110
	10.9	ON-GOING ROCKBOLTING AT THE MINE .....	114
	10.10	GEOTECHNICAL CONCLUSIONS .....	115
11		SRK UNDERGROUND MINE DESIGN .....	116
	11.1	Introduction .....	116
	11.2	Current Mine Plan and Design .....	116
	11.3	SRK Face Design .....	117
	11.4	Developments.....	119
12		ELECTRICAL REVIEW.....	121
	12.1	BACKGROUND .....	121
	12.2	ELECTRICAL DISTRIBUTION REVIEW .....	122
	12.2.1	MVA Capacity .....	123
	12.2.2	Fault Level and Distribution Systems .....	124
	12.2.3	Seruci Coal Face Supply .....	124
	12.2.4	Limitations .....	127
	12.2.5	Nuraxi Figus Coal Face Supply .....	127
	12.2.6	General Comments.....	128
	12.3	CONCLUSIONS AND RECOMMENDATIONS.....	131
13		COAL PREPARATION PLANT .....	133
	13.1	DESCRIPTION OF THE COAL PREPARATION PLANT .....	133
	13.2	REVIEW COMMENTS ON THE PREPARATION PLANT.....	135
	13.3	MAJOR ITEMS OF PROCESSING EQUIPMENT.....	136
	13.3.1	Assumed Basis for Plant Operation and Capacity .....	136
	13.3.2	ROM Handling and Breaking Section .....	136
	13.3.3	Stacker/Reclaiming Plant .....	137
	13.3.4	Drewboy Dense Medium Separator.....	137
	13.3.5	TriFlo Separators .....	138
	13.3.6	Spiral Separators.....	139
	13.3.7	Additional Comment on Dewatering Screens.....	140
	13.3.8	Water Clarification Plant .....	140
	13.3.9	Clean Coal Handling System.....	141
	13.3.10	Rejects Handling System .....	141
	13.4	WATER REQUIREMENTS FOR PLANT OPERATION .....	142
	13.5	COAL PREPARATION PLANT THROUGHPUT 1.3 MILLION T/ANNUM.....	143

13.6	COAL PREPARATION PLANT THROUGHPUT 1.7 MILLION T/ANNUM.....	144
13.7	IMPROVEMENT POSSIBILITIES .....	144
13.8	PREPARATION PLANT CONCLUSIONS .....	145
13.9	RECOMMENDATIONS.....	146
14	ECONOMICS.....	147
14.1	Production Schedule .....	147
14.2	Development Schedule.....	148
14.3	Capital Cost Estimates.....	151
14.4	Operating Costs.....	152
14.5	Economic Model.....	153
14.5.1	Sensitivity Analysis.....	157
15	FEASIBILITY STUDY CONCLUSIONS .....	159
16	RECOMMENDATIONS .....	160

TABLE OF CONTENTS

ALL 3

A COVERING LETTER

B OPERATIONAL ISSUES SRK/AMCO

1	Executive Summary
2	Introduction
3	Terms of Reference
4	Description of Current Mine
5	Geology
6	Resource and Reserve Estimates
7	Infrastructure
	• Surface Installations
	• Underground Structure and Installations
8	Hydrogeological and Water Aspects
9	Environment
10	Geotechnical Design- roof support systems
11	SRK Underground Mine Design
12	Electrical Review
13	Coal Preparation Plant
14	Economics
15	Review Conclusions
16	Recommendations

C. AMCO CAPITAL EXPENDITURE PROGRAMME

1. Introduction
2. Operating Capital Expenditure
  - 2.1 Ventilation
  - 2.2 Power Supply
  - 2.3 Coal Production
  - 2.4 Development
  - 2.5 Transport
  - 2.6 Coal Clearance
3. Summary
4. Appendices
  - Appendix 1 - Start Up Capital Expenditure
  - Appendix 2 - Equipment Replacement Capital Expenditure
  - Appendix 3 - Electrical Layout Drawings
  - Appendix 4 - Underground Transport Routes
  - Appendix 5 - Underground Coal Clearance System

D Amco Operating Costs

1. Operating Cost Evaluation
2. Capital and Operating Cost Model
3. Appendices

Appendix 6: Operating Cost Build-up.

Appendix 7: Amco Capital and Operating Cost Model.

Appendix 8: SRK Capital and Operating Cost Model

E. Amco Alternative Capital Expenditure Proposals

1. Refurbished Plant and Equipment
2. Lease Purchase Arrangements
3. Road Specification Surface Drift Vehicles
4. Power Station Coal Delivery
5. Carbosulcis External Mining Service
6. Installed Equipment Salvage